

LCLS PHOTOINJECTOR

A. Introduction – Jym Clendenin

- 1. Comments on Report of Previous TAC Meeting**
- 2. Current State of Injector R&D**
- 3. Overall Plans and Schedule**

B. Injector Experimental Progress – John Schmerge

GTF experiments results and plans

C. Simulations for Photoinjectors – Cecile Limborg

For current GTF experiments; and

**For LCLS photoinjector—when operating rf gun
with 120 MV/m peak field**

1. Comments on Report of Previous TAC Meeting

•Increased support for injector R&D

Task Force for LCLS Low Emittance Electron Gun formed during period of mystery beam shapes and anomalously high emittances at GTF:

<u>Lowell A. Klaisner</u>	Leader
Jym Clendenin	LCLS Injector Manager
Bob Phillips	Microwave Engineering
Eric Colby	Gun Design
Roger Miller	Beam Dynamics
Paul Bolton	Laser
John Schmerge	GTF

Met November 2000, through February 2001—one more meeting in September 2001.

Useful recommendations for:

Improved diagnostics and beam measurements at GTF;

Load-lock design presented;

Explanations for observed beam shapes discussed. **Now attributed to sharp cross over of gun solenoid pancake windings.**

January 2001, new resources allocated to injector R&D:

New hire of B.S. laser physicist;

2 accelerator physicists added (for spring 2001 only) part-time;

Additional M&S funds sufficient to include upgrade of GTF control and laser systems.

September 2001, additional physicist (Dave Dowell) hired.

• **Beam dynamics and code comparison**

Additional PARMELA simulations for GTF beam have led to many insights.

Simulation specialists have set up group (chaired by Eric Colby, including especially Cecile Limborg and Valentin Ivanov) to compare gun simulations using PARMELA and PIC codes:

PARMELA looking surprisingly good.

2. Current State of Injector R&D

● Gun Test Facility (GTF)

Goals:

The overall goal of the GTF R&D remains a demonstration of $\sim 10^{-6}$ m emittance for a 1 nC beam.

Parameterize beam performance and compare with simulations.

Understand how gun design affects beam performance, e.g., how field balance affects longitudinal emittance.

Significant progress during past year:

Good QE, low dark-current using **single-crystal copper** cathode;

Laser stability, uniformity, reliability greatly improved, but at expense of laser energy;

Better understanding of e^- beam shapes;

Measured emittance for 100 A beam (for <1 nC) matches simulations.

• **LCLS injector plans**

Injector Vault.


The optics for shallow angle (35°) beamline have been worked out:

- **Allows matching under wider range of injector conditions;**
- **More space for diagnostics—including rf kicker for longitudinal emittance studies;**
- **No need to cut notch in vault wall.**

Present design to Radiation Committee in January 2002.

Radiation wall with appropriate penetrations to be installed during summer 2002 linac shutdown.

LCLS Injector



•RF gun

Funding for fabrication of LCLS rf gun not expected until construction funds available in FY04.

Plan is to use a 1.6-cell S-band symmetrized rf gun similar to present GTF gun.

GTF gun designed for 10 Hz. A similar gun with added cooling has been tested in Japan at 50 Hz, but LCLS will operate at 120 Hz.

Additional desired features:

Load lock;

Symmetric rf feed.

Initial conceptual design being done at BNL (Xiji Wang).

Large thermal gradients to be avoided;

Detailed thermal-mechanical simulations under way.

Pre-conceptual load-lock design proposed by Bob Kirby (SLAC).

• **Laser system**

Funding for LCLS Ti:sapphire laser system not expected until construction funds available in FY04.

Development of basic system presently conceived as a 2-year project, with an additional year to finish state-of-the art details.

Begin low-cost R&D this year using existing *Coherent Mira* femtosecond laser in the polarized source lab.

Light shack preparations:

Finish clearing out building at S-20;

Prepare bid package.

3. Plans and Schedule (leading to FY04)

	FY02-1	2	3	4	FT03-1	2	3	4
GTF:								
Control system upgrade	x	x						
Laser system upgrade	x	x						
Basic beam measurements @ 30 MeV		x	x					
Basic beam measurements w/o booster				x	x			
<i>New working point</i> measurements @30 MeV						x	x	x
LCLS Injector:								
Install radiation wall		x						
Prep S-20 gallery room		?	?					
Prepare laser room bid package			x	x				
Install laser clean room					?	?	?	
RF gun conceptual design	x	x	x	x				
Laser R&D		x	x	x	x	x	x	x
Cs ₂ Te Cathode R&D	x	x	x					

John Schmerge will report on GTF results and plans in more detail.

Cecile Limborg will discuss simulations for both GTF and the LCLS injector.